

DITCH PETITION.

London, Ohio, May 17, A.D. 1913, Petition for location, construction, deepening, widening and tiling of a Ditch.

To the Honorable Board of Commissioners, Madison County, Ohio:

The undersigned owners of lots and land which will be drained or benefited by the improvement herein prayed for, hereby make application to your honorable body, and now file with the Auditor of said County, this, their petition, and now and hereby pray for the location, construction, deepening, widening and tiling of a ditch on the route hereinafter set forth.

The necessity for and the benefits of the improvement so prayed for is that it will drain and reclaim the lands along the line thereof and adjacent thereto, and will promote the public health, convenience and welfare.

The following is the beginning, route and termini of said proposed improvement, to-wit: Beginning at the end of a tile drain at the Marysville Pike, and on the North side of the new Dunn Road; thence following an old open ditch or as near thereto as practical, through the lands of McElden Dun and Woodrow Parker, et al., in a general south easterly direction, to the line between said Parker and the Gwynne heirs, and then terminating in said open ditch, and that said open ditch on land of said heirs, be deepened and widened far enough to give a good and sufficient outlet. Also a lateral ditch begin at the end of a tile drain on the land of O'Donnell Bros. near their east line, following an open ditch in a westerly direction through lands of said O'Donnell Bros., and said Parker et al., to the junction of the same with the main ditch above described.

The Names of all Persons and Corporations, either public or private, who in the opinion of the petitioners are in any way affected or benefited thereby are as follows:

- | | |
|--------------------|-----------------|
| Foster B. Houston | George Haines |
| McElden Dun | Thomas Riley |
| Madison County | Perry Walley |
| Richard S. Woodrow | Mike Conway |
| Daniel O'Donnell | Henry Dillion |
| John O'Donnell | John Crabbe |
| C. C. Hankinson | William Minnick |
| Mabel Hamilton | |

Karl E. Burr and W.C. Williard of Columbus, Ohio, and Franc C. Brown of Worthington, Ohio, as Trustees under item 16 of the last will and testament of Edminston Gwynne, deceased.

McEldin Dun)Petitioners.

FILED
MAY 17 1913,
H. M. CHANEY,
Auditor.

#

The Dun No. 1 Ditch Improvement.

PETITIONER'S BOND.

KNOW ALL MEN BY THESE PRESENTS, That McEldin Dun as principal, and Thomas Riley and Geo. H. VanWagener as sureties, are held and firmly bound unto the State of Ohio in the penal sum of Two Hundred Dollars, good and lawful money; for which we bind ourselves, and our heirs, executors and administrators.

Signed by us and dated this 17th day of May, A.D.1913.

The condition of the above obligation is such, nevertheless, that, whereas, on the 17 day of May, A.D.1913, the above bounden McEldin Dun made application to the Commissioners of Madison County, and on said day filed with the Auditor of said County and he petitioned for location, construction, deepening, widening and tiling of a ditch in pursuance of the statute in such case made and provided, on the following route and termini, to-wit:

Beginning at the end of a tile drain at the Marysville Pike, and on the North side of the new Dunn Road; thence following an old open ditch or as near thereto as practical, through the lands of McElden Dun and Woodrow Parker, et al. in a general South easterly direction, to the line between said Parker and the Gwynne heirs, and then terminating in said open ditch, and that said open ditch on land of said heirs, be deepened and widened far enough to give a good and sufficient out let. Also a lateral ditch begin at the end of a tile drain on the land of O'Donnell Bros. near their east line, following an open ditch in a westerly direction through lands of said O'Donnell Bros. and said Parker et al., to the junction of the same with the main ditch above described.

Now if the above bounden McEldin Dun shall pay all costs, if the prayer of said petition be not granted, or if for any other cause the same shall be dismissed, then this obligation shall be void.

The above bond and the sureties thereon, are approved by me this 17th day of May, A.D.1913. McEldin Dun, Thomas Riley, Geo. H. VanWagener. H.M.Chaney, County Auditor.

FILED MAY 17, 1913, H.M. CHANEY Auditor.

: # # # #

NOTICE TO COMMISSIONERS.

OF PETITION FILED AND TIME FOR HEARING.

Office of Auditor of Madison County, O., May 19, A.D.1913.

To the Honorable Board of Commissioners of said County:

GENTLEMEN: You are hereby notified that a petition and bond for a ditch improvement has been filed in this office on the 17th day of May, 1913, a copy of which petition is attached below; and as required by law I have fixed the 10th day of June, 1913, at 10 o'clock, A.M., at the beginning of said proposed ditch described in said petition, for your hearing of said matter.

H.M.Chaney, Auditor.

COPY OF DITCH PETITION.

London, Ohio, May 17th, A.D.1913, Petition for location, construction, deepening, widening and tiling of a Ditch.

To the Honorable Board of Commissioners, Madison County, Ohio:

The undersigned owners of lots and land which will be drained or benefited by the improvement herein prayed for, hereby make application to your honorable body, and now file with the Auditor of said County, this, their petition, and now and hereby pray for the location, construction, deepening, widening and tiling of a ditch on the route hereinafter set forth.

The necessity for and the benefits of the improvement so prayed for is that it will drain and reclaim the lands along the line thereof and adjacent thereto, and will promote the public health, convenience and welfare.

The following is the beginning, route and termini of said proposed improvement, to-wit: Beginning at the end of a tile drain at the Marysville Pike, and on the North side of the new Dunn Road; thence following an old open ditch or as near thereto as practical, through the lands of McElden Dun and Woodrow Parker, et al., in a general south easterly direction, to the line between said Parker and the Gwynne heirs, and then terminating in said open ditch, and that said open ditch on land of said heirs be deepened and widened far enough to give a good and sufficient outlet. Also a lateral ditch begin at the end of a tile drain on the land of O'Donnell Bros., near their east line, following an open ditch in a westerly direction through lands of said O'Donnell Bros., and said Parker et al., to the junction of the same with the main ditch above described.

The Names of all Persons and Corporations, either public or private, who in the opinion of the petitioners are in any way affected or benefited thereby are as follows:

- | | |
|--------------------|-----------------|
| Foster B. Houston | George Haines |
| McElden Dun | Thomas Riley |
| Madison County | Perry Walley |
| Richard S. Woodrow | Mike Conway |
| Daniel O'Donnell | Henry Dillion |
| John O'Donnell | John Crabbe |
| C. C. Hankinson | William Minnick |
| Mabel Hamilton | |

Karl E. Burr and W.C. Williard of Columbus, Ohio, and Franc C. Brown of Worthington, Ohio, as Trustees under item 16 of the last will and testament of Edminston Gwynne, deceased. McEldin Dun) Petitioners.

FILED
MAY 17, 1913,
H.M. CHANEY,
Auditor.

I Hereby Certify the foregoing to be a true copy of a Ditch Petition filed in my office on the 17th day of May, 1913.

H.M. Chaney, County Auditor.

#

See Commissioners' Journal Vol. 12, page 157, for entry on Petition and Bond filed and time fixed for View.

#

Auditor's Office, Madison County, Ohio.

May 20, A.D. 1913.

In the matter of Ditch Improvement No...)

Petitioned for by McEldin Dun.) Notice to Lot or Land Owners.

To the Lot or Land Owners and to the Corporations, either Public or Private, affected by said Improvement:

You, and each of you, are hereby notified that on the 17th day of May, 1913, McEldin Dun filed a petition with the Auditor of Madison County, the prayer of which is for the location, construction, deepening, widening and tiling of a Ditch on the following startingpoint, route and terminus, to-wit: Beginning at the end of a tile drain at the Marysville Pike, and on the North

The Dun No. 1 Ditch Improvement.

side of the new Dunn Road; thence following an old open ditch or as near thereto as practical through the lands of McEldin Dun and Woodrow Parker, et al., in a general south easterly direction, to the line between said Parker and the Gwynne heirs, and then terminating in said open ditch, and that said open ditch on land of said heirs, be deepened and widened far enough to give a good and sufficient outlet. Also a lateral ditch begin at the end of a tile drain on the land of O'Donnell Bros., near their east line, following an open ditch in a westerly direction through lands of said O'Donnell Bros., and said Parker et al., to the junction of the same with the main ditch above described.

You are also notified that the following time and place have been fixed when and where the Commissioners of said County will meet for the hearing of said petition, to-wit; Tuesday, June 10th, 1913, at 10 o'clock A.M., at the beginning of said proposed ditch improvement, for the purpose of hearing any and all proof offered by any of the parties affected by said ditch improvement, whether the said ditch will be conducive to the public health, convenience and welfare; and whether the route described is the best route; and any and all objections to said proposed ditch improvement.

Any application for compensation or damage, or for any change of route, must be in writing and filed with the Commissioners on or before the day set for hearing.

No further notice of any proceedings in this matter will be given.

H.M.Chaney, Auditor of Madison County.

#

Auditor's Office, Madison County, Ohio.

May 24, A.D. 1913.

The State of Ohio,)
Madison County.)

PROOF OF PERSONAL NOTICE.

On this 24th day of May, 1913, personally came James Minshall who being duly sworn according to law, deposes and says that on the days hereinafter named, he served the annexed notice on the persons hereinafter named, by delivering to each person opposite whose name appears "D" a true copy of the annexed notice; and on those opposite whose name appears "R" by leaving the same at their usual place of residence.

Name of Person Served.	How Served D. or R.	WHEN SERVED.
Daniel O'Donnell	R	May 20, 1913.
John O'Donnell	R	" " "
C. C. Hankinson	D	" 21, "
Mabel Hamilton	D	" 20, "
George Haines		
Thomas Riley	D	May 21, 1913.
Perry Walley	R	" " "
Mike Conway	D	" " "
Henry Dillion	D	" " "
John Crabbe	R	" " "
William Minnick	R	" " "

Madison County
and further this deponent saith not.

James Minshall.

Sworn to by James Minshall before me, and by him subscribed in my presence, this 24th day of May, 1913.

H. M. Chaney,
County Auditor.

#

The State of Ohio,)
 Madison County,) SS.

M.H. Wallace, being duly sworn, says he is the Business Manager of THE LONDON ENTERPRISE, a newspaper printed and in general circulation in said county, and that a notice, of which the annexed is a copy, was published in said newspaper for at least 1 consecutive week prior to the 10 day of June, 1913.

M.H. Wallace

Sworn to and subscribed by said M.H. Wallace this 9th day of June, 1913.

Ella Blizzard
 Dep. Co. Auditor.

Printer's Fees, \$3.75

.....
 DITCH NOTICE.

In the Matter of Ditch Improvement Petitioned for by McEldin Dun.

Notice to Non-Resident Lot or Land Owners.

Auditor's Office, Madison County, Ohio.

May 20, 1913.

To the Lot or Land Owners and to the Corporations, either Public or Private, affected by said Improvement:

You, and each of you, are hereby notified that on the 17th day of May, 1913, McEldin Dun filed a petition with the Auditor of Madison County, Ohio, the prayer of which is for the location, construction, deepening and widening and tiling of a ditch on the following starting point, route and terminus, to-wit:

Beginning at the end of a tile drain at the Marysville pike; and on the north side of the new Dun Road; thence following an old open ditch, or as near thereto as practical, through the lands of McEldin Dun and Woodrow Parker et al., in a general southeasterly direction, to the line between said Parker and the Gwynne heirs, and then terminating in said open ditch, and that said open ditch on land of said heirs be deepened and widened far enough to give a good and sufficient outlet. Also a lateral ditch begin at the end of a tile drain on the land of O'Donnell Bros., near their east line, following an open ditch in a westerly direction through lands of said O'Donnell Bros., and said Parker et al., to the junction of the same with the main ditch above described.

You are also notified that the following time and place have been fixed when and where the Commissioners of said county will meet for the hearing of said petition, to-wit; Tuesday, June 10, 1913, at 10 o'clock A.M., at the beginning of said proposed ditch improvement, for the purpose of hearing any and all proof offered by any of the parties affected by said ditch improvement, whether the said ditch will be conducive to the public health, convenience and welfare; and whether the route described is the best route; and any and all objections to said proposed ditch improvement.

Any application for compensation or damage, or for any change of route, must be in writing and filed with the Commissioners on or before the day set for hearing.

No further notice of any proceedings in this matter will be given.

H.M. CHANEY,

Auditor of Madison County.

London, Ohio, May 23, 1913.

#

See Additional Notice to Lot or Land Owners, page 563.

The Dun No. 1 Ditch Improvement.

See Commissioners' Journal Vol. 12, page 173, Adjourned Hearing on Petition.

#

See Commissioners' Journal entry Vol.12, page 176, Commissioners' Finding on Petition.

#

See Commissioners' Journal entry, Vol.12, page 201, Adjourned Hearing on Engineer's Report.

. . . # # #

See Commissioners' Journal entry, Vol.12, page 212, Adjourned Hearing on Engineer's Report.

#

Auditor's Office, Madison County, Ohio.

In the Matter of Ditch Improvement No.) Sept. 2nd, A.D.1913.

Petitioned for by McEldin Dun.) Report and Schedules of Engineer.

To the Honorable, the Board of Commissioners of Madison County, Ohio:

The undersigned Engineer, in obedience to the direction of your Honorable Body, made on the 16th day of June, 1913, has proceeded in the abovematter, and has made a level and survey of the line of said proposed ditch improvement, and set a stake at every hundred feet numbering down stream; and I have made a note of the intersections of lines and boundaries of lands, township and county lines, land marks, bench marks, and road and railroad crossings; and I herewith make report of the same, with profile, and plat and an estimate of the number of the cubic yards of earth or other substance to be removed, and the cost per cubic yard for each working section on said report indicated and of each section of one hundred feet.

I have also made, and return herewith, a schedule of all the lots and lands, and public and corporate roads and railroads, together with the name of the owners of such railroad companies, and the names of the leasees operating the same, that will be benefited by said improvement; and an apportionment of the cost of location and construction, in money, to each lot and tract of land, road and railroad, according to the benefits which will result to each from the said improvement; and in apportioning the costs of such improvement the benefits to any lots or lands by diking the same in whole or in part, have been by me considered with other benefits; and a specification of the manner in which the improvement shall be made and completed; the number of flood gates, water ways, farm crossings and bridges, including kinds and dimensions thereof; and such other matters as the undersigned deems important. The said survey, level reports and schedules are hereunto attached and made a part hereof.

The following is an itemized cost bill, made by me, in the proper discharge of my duty, under your order.

H.L. McCafferty,	Engineer,	1	days,	at \$5.00 per day,	\$5.00
Jesse Paine,	Rodman,	2	"	" \$2.00 " "	\$ 4.00
Perry Walley,	Chainman,	1	"	" \$2.00 " "	\$ 2.00
James Goldsberry,	"	1	"	" \$2.00 " "	\$ 2.00
Seymour Murphy,	"	1	"	" \$2.00 " "	\$ 2.00
Thomas Riley,	Flag.	1	"	" \$2.00 " "	\$ 2.00
Chas. Lohr,	Deputy,	16	"	" \$4.00 " "	\$64.00
G.T. Clark,	Draftsman,	6	"	" \$3.00 " "	\$18.00
W. R. Rainey,	Deputy	8	"	" \$5.00 " "	\$40.00
Ward Minshall					
Horse and buggy, 2 days @ \$1.50					3.00
Team 1 "					4.00
A.G. Kulp					
Horse and buggy 1 day @ \$2.00					2.00

The Dun No. 1 Ditch Improvement.

Madison Auto Co.		
Livery 1 day		\$2.50
M. B. Irwin		
200- 18" stakes @ 1½	3.00	
200- 12" " " 1¼	<u>2.50</u>	<u>5.50</u>
Total		\$158.00

The foregoing Cost Bill allowed by us.....19..

H.L. McCafferty, Engineer.

) County Commissioners.

REPORT OF ENGINEER. SLOPE--- SCHEDULE "A".

Stake every 100 feet numbered down stream.	Surface Elevation.	Grade Elevation.	Total fall from station 0.	Center Slope.	Cut.	Width on Top.	Cubic Yards.	Course and Distance
B 100.00	--	--	--	--	--			
0 99.16	94.50			4.66	4.66			Begin on North side of Marysville pike 76' from stone @ intersection of Dun road and said pike.
1 99.07	94.38			4.69	3.40			
2 98.82	94.26			4.56	3.43			o To 527
3 98.66	94.14			4.52	3.20			S. 78½° E. 527'
4 98.42	94.02			4.40	3.50			
5 97.83	93.90			3.93	3.33			
+27 98.10	93.87			4.23	---			
6 98.30	93.78			4.52	3.30			527 to 830
7 98.13	93.66			4.47	3.17			1206=Ctr. Dun Road and line between McEidin Dun and Richard S. Woodrow
8 98.13	93.54			4.59	3.16			1206' on Dun
+30 96.92	93.50			3.42	--			
B 99.12	--	--	--	--	--			
9 97.94	93.42			4.52	2.95			330 to 1100
10 97.46	93.30			4.16	2.03			S. 66¾° E. 270'
11 96.88	93.18			3.70	2.77	4 20 2 60		
12 97.03	93.06			3.97	3.55			1100 To 1215
+15 96.94	93.04			3.90	--			S. 51½° E. 115'
13 96.79	92.94			3.85	2.21			1215 To 1400
14 96.77	92.82			3.95	2.05			S. 29¾° E. 185'
15 96.53	92.70			3.83	2.30			
16 96.86	92.58			4.28	1.91			
17 96.45	92.46			3.99	1.80			
18 96.01	92.34			3.67	1.77			
19 96.27	92.22			4.05	2.01			1400 To 2970
20 96.16	92.10			4.06	2.25			S. 21¾° E. 1570'
21 96.05	91.98			4.07	1.76			
.B 99.74	--	--	--	--	--			
22 96.03	91.86			4.17	1.39			
23 95.87	91.74			4.13	1.86			
24 95.96	91.62			4.34	2.23			
25 96.42	91.50			4.92	2.43			
26 95.93	91.38			4.55	1.84			Section No. 6.
27 95.64	91.20			4.38	4.38			

Average depth cut

The Dun No. 1 Ditch Improvement.

Station	REPORT OF ENGINEER.			SLOPE.			Course and Distance.	Cubic Yards	SCHEDULE "A".
	Surface Elevation	Grade Elevation	Depth from station 0.	Entire Depth.	Cut.	width on Bottom.			
28	95.66	91.14		4.52	4.52				
29	95.30	91.02		4.28	4.28				
30	95.30	90.90		4.40	4.40				
31	94.77	90.78	3.72	4.19	4.19				
B	97.26	--	--	--	--				
32	94.73	90.66		4.07	4.07				
33	95.09	90.54		4.55	4.55				
34	94.96	90.42		4.34	4.34				
35	95.09	90.30		4.79	4.79				
36	95.15	90.18		4.97	4.97				
37	94.47	90.06		4.41	4.41				
38	94.59	89.94		4.65	4.65				2970 To 4260
39	94.79	89.82		4.97	4.97				S. 2° E. 1290'
40	94.61	89.70		4.91	4.91				
41	93.92	89.58		4.34	4.34				
42	93.79	89.46		4.33	4.33				
460	94.06	89.39		4.67	2.20				Section No. 5.
B	95.81	--	--	--	--				
43	93.98	89.34		4.64	2.28				
44	93.88	89.22		4.66	2.05				
45	94.16	89.10		5.06	2.00				4260 To 5140
46	94.30	88.98		5.32	2.10				S. 10 1/2° W. 880'
47	94.09	88.86		5.23	2.23				
48	93.57	88.74		4.87	2.12				
49	92.78	88.62		4.16	2.14				
50	92.76	88.50		4.26	2.06				5140 To 5300
51	92.40	88.38		4.02	1.91				S. 29 1/2° W. 160'
40	92.71	88.33		4.38	--				5880= Line bet. Woodrow and Gwynne
52	92.46	88.26		4.20	2.18				4674' on Woodrow
53	92.23	88.14		4.09	2.50				5300 To 5400
B	94.75	--	--	--	--				S. 51° W. 100'
54	93.20	88.02		5.18	2.54				
55	92.69	87.90		4.79	2.31				
56	92.42	87.78		4.64	2.52				
57	92.28	87.66		4.62	2.42				
58	91.98	87.54		4.44	2.66				5400 To 6100
59	92.86	87.42		5.44	2.68				S. 58° W. 700'
60	92.83	87.30		5.03	2.55				
B	95.65	--	--	--	--				6100 To 6200
61	93.09	87.18		5.91	2.59				S. 42° W. 100'
62	92.86	87.06		5.80	2.10				
63	92.73	86.94		5.79	1.76				6200 To 6400
450	92.80	86.88	7.62	5.92	1.67				Section No. 4 S. 29 1/2° W. 200'

New Cut

New Cut.

Average Depth 4.50
do. cut. 4.60

Average depth 5.00
do. cut 2.25

The Dun No. 1 Ditch Improvement.

REPORT OF ENGINEER.				SLOPE.		SCHEDULE "A".
<i>Stake every 100 feet measured down stream.</i>	Surface Elevation.	Grade Elevation	Total fall from Station 0	Entire Depth	cut.	Course and Distance.
Main Ditch Open.						
63+50	92.80	86.38	6.42	2.17		
64	91.31	86.33	4.98	1.70		6400 To 6600
65	90.78	86.23	4.55	1.80		S. 13° E. 200'
66	90.33	86.13	4.20	1.49		
67	90.33	86.03	4.30	1.36		
68	90.14	85.93	4.21	1.46		6600 To 7550
69	89.96	85.83	4.13	1.20		S. 30 1/2° E. 950'
70	90.10	85.73	4.37	.98		
71	90.21	85.63	4.58	1.29		
72	90.12	85.53	4.59	1.38		
73	89.64	85.43	4.21	1.12		7550 To 7800
74	89.49	85.33	4.16	1.09		S. 16 1/2° E. 250'
75	89.55	85.23	4.32	.80		
B	93.93	--	--	--		
76	89.68	85.13	4.55	1.18		
77	89.48	85.03	4.45	1.50		7800 To 8315
78	88.65	84.93	3.72	1.35		S. 23° W. 515'
79	89.52	84.83	4.69	.83		
80	89.17	84.73	4.44	.46		
81	80.20	84.63	4.57	.88		
82	83.37	84.53	4.84	.62		
83	89.61	84.43	5.18	1.10		
B	91.08	--	--	--		10127- Line bet.
84	88.91	84.33	3.58	--		8315 To 9300 Gwynne & Stone
85	89.55	84.23	5.32	.88		S. 32 1/2° E. 985' 4247' on Gwynne
86	89.76	84.13	5.63	.70		
87	89.26	84.03	5.23	.71		
88	89.02	83.93	5.09	.88		
89	89.21	83.83	5.38	1.21		
90	89.08	83.73	5.35	1.05		
91	89.22	83.63	5.59	1.42		
92	88.93	83.53	5.40	1.50		9300 To 9775
93	88.77	83.43	5.34	1.81		S. 83 1/2° E. 475'
94	88.16	83.33	4.83	1.63		
95	88.07	83.23	4.84	1.25		
96	88.56	83.13	5.43	1.40		
97	87.98	83.03	4.95	.90		
98	87.31	82.93	4.38	1.35		
99	87.68	82.83	3.55	4.85	.97	
100	87.56	82.73	4.83	1.32		Section No. 3.
101	87.25	82.58	4.67	1.34		813 CU.Yds.
+27	--	--	--	--	--	
B	90.03	--	--	--	--	
102	87.26	82.43	4.83	1.58		9775 To 10250
103	86.79	82.28	4.51	1.26		S. 41 1/2° E. 475'

The Dun No. 1 Ditch Improvement.

REPORT OF ENGINEER.				SLOPE.		Course and Distance.	SCHEDULE "A".
Stake every 100 feet measured down stream.	Surface Elevation.	Grade Elevation.	Total fall from station 0.	Entire Depth.	Cut.		
104	86.95	82.13		4.82	1.25		
105	86.55	81.98		4.57	1.92		
106	86.70	81.83		4.87	1.82		
107	86.20	81.68		4.52	1.97		10250 To 110
108	86.47	81.43		4.94	1.54		S. 27° E. 750'
109	85.89	81.38		4.51	1.37		
110	85.33	81.23		4.10	1.09		
111	86.20	81.08		5.12	1.49		
112	85.91	80.93		4.98	1.66		
113	85.57	80.78		4.79	1.77		
114	85.73	80.63		5.10	1.52		110 To 12315
115	85.67	84.48		5.19	1.49		S. 29½° E. 1315'
116	84.84	80.33		4.51	1.48		
117	86.16	80.18		5.98	1.52		
B	86.83	--	--	--	--		
118	85.56	80.03		5.53	1.31		
119	85.54	79.88		5.66	1.23		12609= Line bet.
120	83.01	79.73		3.28	1.83		Stone and Campbell
121	83.81	79.58		4.23	1.16		12315 To 127 2482' on Stone
122	83.98	79.43		4.55	1.79		S. 12½° W. 385'
123	83.11	79.28		3.83	1.54		
124	82.72	79.13		3.59	1.39		
125	83.03	78.98		4.05	1.10	Section No. 2	127 To 129
126	82.53	78.83		3.70	1.76	1100 Cu.Yds.	S. 17° W. 200'
127	81.49	78.68		2.81	1.51		
128	82.41	78.53		3.88	1.46		129 To 131 13122= Line bet.
129	81.57	78.38		3.19	1.23		S. 23½° W. 200' Campbell and Harper
130	81.10	78.23		2.87	1.41		513' on Campbell
131	80.71	78.08		2.63	1.48		
B	86.67	--	--	--	--		
132	82.14	77.93		4.21	--		131 To 13336 214' on Harper
133	83.09	77.78 7.40		5.31	--		S. 32° W. 236'
+36	82.99	77.64	8.74	5.35	--	Section No. -1.	643 Cu.Yds.

The Dun No. 1 Ditch Improvement.

REPORT OF ENGINEER.				SLOPE.			SCHEDULE "A".
<i>Stake every 100 feet numbered above stream</i>	Surface Elevation,	Grade Elevation,	Total fall from station 0,	Entire Depth,	Cut.	Width on Bottom, width on Top,	Course and Distance.
Lateral No. 1 @ 4260							
B	98.37	--	--	--	--	--	
0	96.59	92.45		4.14	1.32		0. To 355
1	97.66	92.35		5.31	2.77		S. 29° E. 355'
2	97.55	92.25		5.30	2.59		Begin on lands of Daniel and John O'Donnell
3	97.17	92.15		5.02	2.47		
+55	97.47	92.10	--	--	--	--	
4	97.52	92.05		5.47	2.41		
5	97.08	91.95		5.13	2.50		355 To 700
6	96.92	91.85		5.07	2.55		N. 60° E. 345'
7	96.68	91.75		4.93	2.62		1303- Line bet.
8	97.32	91.65		5.67	2.58		700 To 820
+20	97.18	91.58	--	--	--	--	N. 26½° E. 120'
9	96.78	91.55		5.23	2.77		820 To 900
+85	96.26	91.53	--	--	--	--	N. 59½° E. 80'
10	96.50	91.45		5.05	2.58		900 To 985
11	96.56	91.35		5.21	2.66		N. 82½° E. 85'
B	96.32	--	--	--	--	--	
12	96.14	91.25		4.89	2.25		
13	96.11	91.15		4.96	2.06		985 To 1500
14	95.49	91.05		4.44	2.02		S. 51° E. 515'
15	94.79	90.95		3.84	1.63		1500 To 1600
16	94.03	90.85		3.18	--		N. 82¼° E. 100'
30	95.29	90.78	--	--	--	--	1142' on Woodrow
17	95.67	90.75		4.92	1.86		1600 To 1750
+50	95.76	90.70	--	--	--	--	N. 43½° E. 150'
18	95.52	90.65		4.87	1.86		
19	95.55	90.55		5.00	2.04		1750 To 2030
20	95.13	90.45		4.68	1.73		N. 8° E. 280'
+30	94.88	90.38	--	--	--	--	
21	95.02	90.35		4.67	1.76		
22	94.59	90.25		4.34	1.66		2030 To 2445
23	94.53	90.15		4.38	1.46		N. 44¼° E. 415'
24	94.27	90.05		4.22	1.42		
+45	94.07	90.00	2.45	4.07	1.61		Section No. 7.
B	95.81	--	--	--	--	--	

Average Depth 4.84 do cut 2.13

The Dun No. 1 Ditch Improvement.

REPORT OF ENGINEER.				SLOPE.			SCHEDULE "A".
Stake every 100 feet but none placed between stations.	Surface Elevation.	Grade Elevation.	Total fall from station 0	Entire Depth.	Cut.	Width on Top. Cubic Yards.	Course and Distance.
Lateral No. 2 @ 6350.							
B 98.93	--	--	--	--	--		
0 96.50	90.00	90.00		6.50	3.03		Begin on lands
1 96.23	89.88	89.88		6.35	3.03		of Richard S. Woodrow
2 95.93	89.76	89.76		6.17	2.77		
3 95.50	89.64	89.64		5.86	2.81		
4 95.16	89.52	89.52		5.64	2.64		0 To 720
5 94.89	89.40	89.40		5.49	2.52		S. 21 $\frac{3}{4}$ ° E. 720'
6 94.88	89.28	89.28		5.60	2.52		
7 94.42	89.16	89.16		5.26	2.26		
+20 94.58	89.14	--	--	--	--		
8 94.21	89.04	89.04		5.17	2.47		720 To 985
9 94.26	88.92	88.92		5.34	2.38		S. 111 $\frac{1}{2}$ ° E. 265'
B 95.63	--	--	--	--	--		2070= Line bet.
+85 93.86	88.82	--	--	--	--		Woodrow and
10 93.91	88.80	88.80		5.11	2.13		Gwynne
11 93.70	88.68	88.68		5.02	2.47		2070' on Woodrow.
12 93.78	88.56	88.56		5.22	2.65		985 To 1700
13 93.33	88.44	88.44		4.89	2.48		S. 77 $\frac{1}{2}$ ° E. 715'
14 92.75	88.32	88.32		4.43	2.56		
15 92.25	88.20	88.20		4.05	2.59		1700 To 1800
16 91.95	88.08	88.08		3.87	2.45		S. 19° E. 100'
17 93.45	87.96	87.96		5.49	2.54		430' on Gwynne.
18 92.95	87.84	87.84		5.11	2.25		1800 To 2100
19 91.37	87.72	87.72		3.65	2.01		S. 4 $\frac{1}{2}$ ° W. 300'
20 91.13	87.60	87.60		3.53	1.91		
21 90.36	87.48	87.48		2.88	2.03		2100 To 2300.
22 90.59	87.36	87.36		3.23	1.50		S. 13 $\frac{1}{4}$ ° E. 200'
23 90.59	87.24	87.24		3.35	1.61	23 To 24	
24 92.30	87.12	87.12		--	5.18	New Cut	2300 To 2500
25 92.80	86.88	86.88	3.12	5.92	1.77	Section No. 8.	S. 12 $\frac{1}{2}$ ° E. 200'
B 95.65	--	--	--	--	--		

Average Depth 4 $\frac{9}{16}$ do cut 2 $\frac{5}{16}$

#

The Dun No. 1 Ditch Improvement.

Report of Engineer.

Schedule AA.

Statement of Working Sections of the Dun Ditch No. 1.

No. of Working Sections	No. of Stakes.		No. of Linear Feet	No. of Cubic Yards	Price Per Yard	Amount	Remarks	
	From	To						
<u>Main Ditch</u>								
<u>Open.</u>								
1	133+36	125	836	643	25¢	\$160.75		
2	125	100	2500	1100	25¢	275.00		
3	100	63+50	3650	813	25	203.25		
Total						639.00		
<u>Main Ditch</u>								
<u>Tile.</u>								
4	63+50	42+60	2090					
	126.67	Rods	18" Tile @	4.20		532.01		
	126.67	"	Construction	1.50		190.00	Average Cut 2.25	
Total						722.01		
5	42+60	26	1660					
	100.61	Rods	15" Tile @	2.80		281.71		
	100.61	"	Construction	2.25		226.37	Average cut 4.50	
Total						508.08		
6	26	0	2600					
	157.57	Rods	12" Tile @	1.65		260.00	Average cut 2.60	
	157.57	"	Construction	1.00		157.57		
Total						417.57		
<u>Lateral No. 1 @ Sta. 42+60.</u>								
7	2445	0	2445					
	148.18	Rods	12" Tile @	1.65		244.50		
	148.18	"	Construction	.75¢		111.14	Average cut 2.13	
Total						355.64		
<u>Lateral No. 2 @ Sta. 63+50</u>								
8	25	0	2500					
	151.51	Rods	15" Tile @	2.80		424.23		
	151.51	"	Construction	1.25		189.39	Average cut 2.50	
Total						613.62		
<u>Concrete Bulkhead.</u>								
9	<u>@ Sta. 63+50 of Main.</u>							
	Estimate					100.00		
	Estimate for Y's					100.00		

The Dun No. 1 Ditch Improvement.

Report of Engineer.

Schedule AA.

Statement of Working Sections of the Dun Ditch No. 1.

Price per yard
amount

Recapitulation.

Main Open Ditch Construction

2556 CU. Yds. @ .25 \$639.00

Main Tile Ditch Construction.

126.67 Rods Const. @ 1.50 190.00

100.61 " " " 2.25 226.37

157.57 " " " 1.00 157.57

Lateral No. 1.

148.18 Rods Const. @ .75 111.14

Lateral No. 2.

151.51 Rods Const. @ 1.25 189.39

Total 874.47

Tile Estimate.

126.67 Rods 18" Tile @ 4.20 532.01

252.12 " 15" " " 2.80 705.94

305.75 " 12" " " 1.65 504.50

Total 1742.45

Totals.

Open Construction 639.

Tile do 874.47

Tile 1742.45

Concrete 100.00

Vitrified Y's 100.00

Grubbing 25.00

Superintending Const.

Assistant's, livery, etc. 200.00

Additional material or labor

that may be needed 100.00

Total 3780.92

#

The Dun No. 1 Ditch Improvement.

REPORT OF ENGINEER.
OWNER'S NAME AS
FOUND ON DUPLICATE.

	Survey	Description	Acres Owned	Acres Benefited	Estimated Cost of Construction	SCHEDULE "B" Estimated Cost of Location	Total Cost "B" apportioned
	12146	DeerCreek Tp.	416.	25.	\$ 75.00	\$ 3.15	\$ 78.15
	12146	" " "	416.	100.	200.00	8.40	208.40
	12067)	Monroe TP.Sch.124.	124.	10.	100.00	4.20	104.20
	12142)	" " "	86.51	20.	100.00	4.20	104.20
	12153)	" " "					
M	12176)	DeerCreek Tp.	81.	35.	288.00	12.10	300.10
M	7560	" " "	228.06	150.	1230.00	51.66	1281.66
#1	12176)	" " "	81.	21.	75.00	3.15	78.15
#1	7560	" " "	228.06	20.	75.00	3.15	78.15
#2	7560	" " "	228.06	58.	300.00	12.60	312.60
M	4750	" " "	214.	205.	145.00	6.09	151.09
M	6646	" " "	202.35	200.	140.00	5.88	145.88
M	6317	" " "	370.00	300.	215.00	9.03	224.03
#2	6317	" " "	370.	70.	150.00	6.30	156.30
#2	12146	" " "	52.50	25.	50.00	2.10	52.10
M	6646	" " "	108.	108.	112.00	4.70	116.70
"	3901	" " "	1.20	1.20	1.00	.04	1.04
"	4751	" " "	7.00	7.00	7.00	.30	7.30
M	12142)	" " "	158.	50.	50.00	2.10	52.10
	12153)	" " "					
M	12142)	" " "	171.88	20.	25.00	1.05	26.05
	12153)	" " "					
M	12142)	" " "	171.88	20.	20.	.84	20.84
	12153)	" " "					
M	12142)	" " "	60.	20.	20.00	.84	20.84
	12153)	" " "					
#1	7560	D.C.& MonroeSch18.	18.	18.	150.00	6.30	156.30
	12142)	" " "	36.11	22.51	175.00	7.35	182.35
	12153)	" " "					
#1	12142)	" " "	49.08	23.	30.00	1.26	31.26
	12153)	" " "					
M	3901	Herbert H.and Pearl Harper			10.00	.42	10.42
		Madison County			37.92	.79	38.71
					<u>3780.92</u>	<u>158.00</u>	<u>3938.92</u>

#

The Dun No. 1 Ditch Improvement.

Report of Engineer.

Schedule "C".

Auditor's Office, Madison County, Ohio.

.....A.D.191. .

In the matter of Dun No. 1 Ditch. . .)

Improvement, Petitioned for by McEldin Dun.) Specifications of the Manner of Construction.

DUN DITCH NO.1.

This improvement shall be constructed a tile ditch from station 0 to station 63+50 of the main ditch, and an open ditch from station 63+50 to station 133+36 its terminus.

Sizes of Tile.

The tile to be used in the main ditch shall be, from station 0 to station 26 12" tile, inside diameter; and from station 26 to station 42+60 15" tile, inside diameter; and from station 42+60 to station 63+50 18" tile, inside diameter.

Lateral No. 1 shall be tiled with 12" tile.

Lateral No. 2 shall be tiled with 15" tile.

Open Ditch.

The Open Ditch shall be made 2 feet wide on the bottom and shall have side slopes of 1 1/2 to 1 as nearly as practicable. All dirt taken from the open ditch to be removed 15 feet from the top of the banks and well scattered.

The trench for receiving the tile shall be cut down to the grade line as shown on the profile filed herewith, and as indicated in Schedule "A" of this report.

The tile to be evenly laid and closely jointed so as to prevent sediment from entering the tile.

The tile must not be covered until they have been inspected by the engineer in charge of the work. After inspection there shall be placed on the tile sufficient dirt to protect them from injury by freezing, by being tramped by stock or by farming over them, and if the dirt taken from the trench is not sufficient, the banks shall be plowed down and in, to complete the filling to the satisfaction of the Engineer.

The contractor for constructing the tile ditch shall put in place all Ys, and connect all laterals, old or new, without extra compensation, except where any lateral needs taking up and cleaning or relaying for more than one rod from the Main Ditch, then, in such instance, he shall be allowed a reasonable compensation for said work, to be determined by the Engineer.

Tile.

All tile shall be of first class quality of Drain Tile, and shall be delivered on the line of the ditch, each size in its proper place, also all Ys for connection shall be delivered in their proper place. Any expense caused the contractor for construction by failure to deliver, or by improper delivery of tile or Ys will be charged against the tile contract and deducted therefrom at the time of settlement.

Grubbing.

All brush along the banks of the open ditch must be removed by the contractor by grubbing and all timber larger than 6 inches standing within 15 feet of the ditch shall be deadened.

Bulkhead.

At station 63+50 of Main Ditch there will be constructed a Concrete Bulkhead with spillway, apron and wing. The concrete to be 1 part Portland Cement to 5 parts clean, medium, coarse gravel. Said wall to be built as per instruction of the engineer.

Right-of-Way.

A Clear Right-of-Way of 30 feet on each side of the ditch is reserved for the delivery of the tile and the construction of the ditch.

#

The Dun No. 1 Ditch Improvement.

Commissioners' Office,

London, Ohio, Sept. 2ⁿ, 1913.The foregoing report approved as submitted this 2ⁿ day of Sept. 1913.

E.C. Breyfogle) Commissioners
 E.E. Willard) of
 Jas. F. Martin) Madison County, Ohio.

#

See Commissioners' Journal entry, Vol. 12, page 228, Finding of Commissioners
 on Report of Engineer.

#

DITCH SALE.

NOTICE TO CONTRACTORS.

The undersigned County Surveyor will sell at public outcry to the lowest and
 best bidder on Tuesday, September 23, 1913, at 10 o'clock a.m., standard time, at
 the County Surveyor's office in the basement of the court house, at London, the
 labor of constructing and furnishing all necessary materials for The Dun Ditch No. 1,
 located in Deercreek Township, three miles northwest of Lafayette.

MAIN DITCH.

Section 1.	From Station 133+36 to Station 125 = 836 feet. Open work- 643 cubic yards at 25c		\$ 160.75
Section 2.	From Station 125 to Station 100 = 2500 feet. Open work- 1100 cubic yards at 25c		\$ 275.00
Section 3.	From Station 100 to Station 63+50 = 3650 feet. Open work- 813 cubic yards at 25c		\$ 203.25
Section 4.	From Station 63+50 to Station 42+60 = 2090 feet. 126.67 rods 18-inch tile at \$4.20	\$532.01	
	126.67 rods construction at \$1.50 Average cut, 2 feet 3 inches.	190.00	\$ 722.01
Section 5.	From Station 42+60 to Station 26 = 1660 feet. 100.61 rods 15-inch tile at \$2.80 100.61 rods construction at \$2.25 Average cut, 4 feet 6 inches.	\$281.71 \$226.37	\$ 508.08
Section 6.	From Station 26 to Station 0 = 2600 feet. 157.57 rods 12-inch tile at \$1.65 157.57 rods construction at \$1.00 Average cut, 2 feet 7 inches.	\$260.00 \$157.57	\$ 417.57

Lateral No. 1 at Station 42+60 on Main:

Section 7.	From Station 24+45 to Station 0 = 2445 feet. 148.18 rods 12-inch tile at \$1.65 148.18 rods construction at 75c Average cut, 2 feet 2 inches.	\$244.50 \$111.14	\$ 355.64
------------	--	----------------------	-----------

Lateral No. 2 at Station 6350 on Main.

Section 8.	From Station 25 to Station 0 = 2500 feet. 151.51 rods 15-inch tile at \$2.80 151.51 rods construction at \$1.25 Average cut, 2 feet 6 inches.	\$424.23 \$189.39	\$ 613.62
------------	--	----------------------	-----------

Recapitulation.

305.75 rods 12-inch tile at \$1.65	\$504.50
252.12 rods 15-inch tile at \$2.80	705.94
126.67 rods 18-inch tile at \$4.20	<u>532.01</u>
Total Tile	\$1,742.45
2556 cubic yards open work at 25c	\$ 639.00
684.54 rods construction	<u>874.47</u>
Total	\$3,255.92

Bidders are required to deposit \$25 cash-- no checks taken-- before any bid will
 be considered. Contract and bond must be entered into within five days from date
 of sale.

The Dun No. 1 Ditch Improvement.

Persons desiring to view the ditch should do so prior to time of sale.
 Specifications now on file in the Auditor's office at London, Ohio.
 The right to reject any or all bids is reserved.

By order County Commissioners of Madison County, Ohio.

H.M.Chaney, Auditor.

H.L. McCafferty, County Surveyor.

PLEASE POST.

#

Auditor's Office, Madison County, Ohio.

Sept. 23, A.D.1913.

In the matter of Ditch Improvement No..)

Petitioned for by McEldin Dun.

) Report of Sale of the Labor of Construction.

To the Honorable Commissioners of Madison County, Ohio:

Gentlemen. In obedience to your direction and also in pursuance of the notice, duly given by the Auditor of the sale of the work of constructing the above styled improvement, at the time and place therein specified, I offered the said several working sections for sale to the lowest responsible bidder at public outcry and sold the same to the persons hereinafter named, at the prices herein stated, and took their contracts and bonds respectively conditioned according to law, and return the same herewith for your approval.

No. of Working Sections.	TO WHOM SOLD.	Amount for which it sold.	Amount for which it was estimated.	WHEN TO BE COMPLETED.
1-2-3	S.A. Willoughby	\$637.00	\$639.	Dec. 1st, 1913.
4-5-6-7-8	Cantwell Bros.	867.	874.47	Jany. 1st, 1914.
Tile	Madison Tile Co.	1688.00	1742.45	" " "
9	Bulkhead		100.00	
Ys	American Sewer Pipe Co.		100.00	

I certify the above to be correct.

H.L.McCafferty, County Surveyor.

#

CONTRACT.

This agreement made and entered into this 23rd day of September, A.D.1913, by and between the Commissioners of Madison County, Ohio, party of the first part, and S.A.Willoughby Contractor party of the second part, Witnesseth:

That the party of the second part hereby agrees with the party of the first part for and in consideration of the sum of six hundred thirty seven Dollars, hereafter to be paid and under the penalty expressed in a bond bearing even date with these presents and hereto attached, to furnish at his own expense all the necessary materials, labor and tools to build, construct and complete, in a good, substantial and workmanlike manner, and in accordance with the plans and specifications hereto attached, the following:

Dun Ditch No. 1.

Sections 1-2-3.

2556 cu.yds. open work.

The Contractor shall remove all surplus earth from ditch and evenly spread the same as per specifications.

The Contractor shall be responsible for injuries to persons and property inflicted during the prosecution of the work, and the County shall in nowise be liable therefor.

The Contractor agrees to conform to the direction of said Commissioners, or other

persons appointed by them to take charge of the work, and any increase or decrease in material or labor ordered by them shall be calculated at the same rate as required in original plans and specifications . . .

The party of the first part agrees, upon the completion of said work as above specified, that they will cause an order to be drawn by the Auditor of said County on the Treasurer of said County payable to the party of the second part, for such sum as may be due him upon the actual measurement of the work.

If it becomes necessary to increase or diminish the amount of work stipulated in this contract, then the amount of such increase or reduction will be estimated at the rate of the contract and allowed or deducted as the case may be.

Work to begin at once, and to be fully completed on or before December 1st, 1913.

S.A. Willoughby
Contractor.

E.E. Willard

Geo. Fitzgerald

P.M. Gregg

Commissioners Madison County, Ohio.

See page 561 for Bond of S.A. Willoughby. # # # #

CONTRACT FOR DRAIN TILE.

Auditor's Office, Madison County, Ohio.

In the matter of Ditch Improvement) September 23rd, A.D. 1913.

No. Petitioned for by McElden Dun.) CONTRACT FOR DRAIN TILE.

WHEREAS, The above styled improvement has been duly ordered and advertised for sale according to law, and the construction of Working Sections Nos. 4, 5, 6, 7, 8 of 11295 feet tile 305.75 rods of 12" tile; 252.12 rods of 15" tile; 126.67 rods of 18" tile sold by the County Surveyor, on the 23rd day of September, 1913, to The Madison Tile Co. Now, in consideration of the premises, it is agreed by me, to and with whomsoever may be interested therein, that I will furnish 305.75 rods of 12 inch Drain Tile from Station . . . to Station . . . ; and 252.12 rods of 15 inch Drain Tile from Station . . . to Station . . . ; and 126.67 rods of 18 inch drain tile delivered on line of above styled improvement in lots as ordered, the same to be delivered on or before the 1st day of January, 1914; provided this contract shall be of no force and effect until approved by the Board of Commissioners of Madison County, Ohio.

H.L. McCafferty
County Surveyor.

Madison Tile Co.
Contractor.

#

CONTRACTOR'S BOND FOR DRAIN TILE.

Auditor's Office, Madison County, Ohio.

In the matter of Ditch Improvement) September 23rd, A.D. 1913.

No. Petitioned for by McElden Dun.)

KNOW ALL MEN BY THESE PRESENTS, That The Madison Tile Co. as principal and S.S. VanCleve and Minnie H. VanCleve as sureties are firmly held and bound unto the State of Ohio, in the penal sum of three thousand three hundred and seventy-six Dollars, good and lawful money.

Signed and dated this 23rd day of September, 1913.

THE CONDITION OF THE ABOVE OBLIGATION is such, however, that whereas, the above bounden principal contractor has bid off the furnishing and delivering the Drain Tile for constructing Working Section Nos. 4, 5, 6, 7, 8 have duly entered into the annexed contract, subject to the condition that the same shall be approved by the Commissioners of said County.

The Dun No. 1 Ditch Improvement.

Now, if the said The Madison Tile Co. shall well and truly perform all the obligations of his said contract and complete the same within the time fixed by said contract and pay all damage which may occur by reason of a failure to complete the same within the time agreed upon in said contract, then this obligation shall be void, otherwise to be in full force and effect in law.

Madison Tile Co.
By S.S. Van Cleve
Minnie H. VanCleve

This Contract and Bond, and Sureties on said Bond approved this 6 day of Oct. 1913.
H.L. McCafferty, County Surveyor. E.E. Willard, President of Board of Commissioners.

See page 560.

BOND.

KNOW ALL MEN BY THESE PRESENTS, That we S.A. Willoughby ... are held and firmly bound unto the State of Ohio for the use of Madison County in the sum of one thousand two hundred seventy four Dollars for the payment of which, well and truly to be made, we jointly and severally bind ourselves, our heirs, executors, and administrators, by these presents.

Subscribed with our hands and sealed with our seals this 23rd day of September, 1913. THE CONDITION OF THIS OBLIGATION is such that whereas the above bound S.A. Willoughby have this day taken of the Commissioners of Madison County the work of constructing sections 1, 2, 3 of Dun. Ditch #1, 2556 cu. yds. open work and agrees to fully complete the work on or before the dates above set forth.

Now, if the said S.A. Willoughby shall well and truly perform said work, agreeably to the above stipulations and conditions, then this obligation to be void; otherwise to be and remain in full force and virtue in law.

The above bond is approved: S.A. Willoughby (Seal)
.....19... P.A. Lanigan (Seal)
Andy Watson (Seal)

Commissioners Madison County, Ohio.

Auditor's Office, Madison County, Ohio.

In the matter of Dun County Ditch No. 1)
Improvement No. Petitioned for by)
McElden Dun, et al.) Contract for Labor of Construction. Sept. 23rd, A.D. 1913.

WHEREAS, The above styled improvement has been duly ordered, and advertised for sale according to law, and the construction of Working Sections Nos. 4-5-6-7-8 of 11295 feet was sold by the County Surveyor, on the 23rd day of September, 1913, to the undersigned, for eight hundred sixty seven Dollars, pursuant to said order and notice. Now, in consideration of the premises, it is agreed by me, to and with whomsoever may be interested therein, that I will do and perform all the labor of constructing said improvement in accordance with the specifications for constructing the same, as shown in the record of the proceedings thereof, the same to be completed on or before the 1st day of January, 1913; Provided, however, this contract shall be of no force and effect until approved by the Board of Commissioners of Madison County, Ohio.

H.L. McCafferty, County Surveyor. Cantwell, Bros. Contractor.

The Dun No. 1 Ditch Improvement.

Auditor's Office, Madison County, Ohio.

Sept. 23rd, 1913.

In the matter of County Ditch)
Improvement No..Petitioned for)
By McEldin Dun et al.)

Contractor's Bond.

Know all Men by These Presents, That Cantwell Bros. as principal, and.....and
.....as sureties, are firmly held and bound unto the STATE OF OHIO, in the penal
sum of one thousand seven hundred thirty four Dollars, good and lawful money.

Signed and dated this 23rd day of September, 1913.

The Condition of the Above Obligation is such, however, that whereas, the above
bounden principal contractors have bid off the labor of constructing Working
Section No. 4-5-6-7-8, have duly entered into the annexed account, subject to the
condition that the same shall be approved by the Commissioners of said Madison
County, and have agreed to fully do and perform all labor of constructing said
improvement in accordance with the plans and specifications of said improvement,
as shown in the record of said proceedings, on or before the 1st day of January,
1913.

Now, if the said Cantwell Bros. shall well and truly perform all the obligations
of their said contract and complete the same within the time fixed by said contract
and pay all damages which may accrue by reason of a failure to complete the same
within the time agreed upon in said contract, and pay for all labor and material
and for all debts incurred in the performance of this contract, then this obligation
shall be void, otherwise to be in full force and effect in law.

Cantwell Bros.

Madison Tile Co.
By S.S. VanCleve
George Bennett.

This Contract and Bond, and Sureties on said Bond, approved this 29 day of Sept.
1913.

H.L. McCafferty
County Surveyor.

E.E. Willard
President of Board of Com'rs.

#

See Commissioners' Journal entry Vol.12, page 246, Approval of Contracts and
Bonds of S.A. Willoughby and Cantwell Bros.

#

See Commissioners' Journal entry Vol.12, page 249 Approval of Contract and
Bond of The Madison Tile Company.

#

London, Ohio, January 8, 1914.

In the Matter of the Dun
Ditch Improvement No. 1.

To the Auditor of Madison County, Ohio:

We hereby make application to pay our entire assessment in cash on the above
styled improvement.

Grace N. Hamilton
Mabel L. Hamilton
(By G.N.H.)

. Filed January 8th, 1914.

H.M. Chaney
Auditor,
Per B.

#

The Dun No. 1 Ditch Improvement.

See page 546.

Auditor's Office, Madison County, Ohio.

In the matter of Ditch Improvement)

August 5, A.D. 1913.

No...Petitioned for by McEldin Dun.) Additional Notice to Lot or Land Owners.

To the Lot or Land Owners and to the Corporations, either Public or Private, affected by said Improvement:

You, and each of you, are hereby notified that on the 17th day of May, 1913, McEldin Dun filed a petition with the Auditor of Madison County, the prayer of which is for the location, construction, deepening, widening and tiling of a Ditch on the following starting point, route and terminus, to-wit:

Beginning at the end of a tile drain at the Marysville Pike, and on the North side of the new Dunn Road; thence following an old open ditch or as near thereto as practical, through the lands of McEldin Dun and Woodrow Parker et al., in a general south easterly direction, to the line between said Parker and the Gwynne heirs, and then terminating in said open ditch, and that said open ditch on land of said heirs be deepened and widened far enough to give a good and sufficient outlet. Also a lateral ditch begin at the end of a tile drain on the land of O'Donnell Bros., near their east line, following an open ditch in a westerly direction through lands of said O'Donnell Bros., and said Parker et al., to the junction of the same with the main ditch above described.

You are also notified that the following time and place have been fixed when and where the Commissioners of said County will meet for the hearing of said petition, to-wit: Tuesday, Sept. 2, 1913, at 10 o'clock A.M., at the Commissioners' Office, London, Ohio, for the purpose of hearing any and all proof offered by any of the parties affected by said ditch improvement, whether the said ditch will be conducive to the public health, convenience and welfare; and whether the route described is the best route; and any and all objections to said proposed ditch improvement.

Any application for compensation or damage, or for any change of route, must be in writing and filed with the Commissioners on or before the day set for hearing.

No further notice of any proceedings in this matter will be given.

H.M.Chaney, Auditor of Madison County.

#

Auditor's Office, Madison County, Ohio.

The State of Ohio,)

Aug. 9th, A.D. 1913.

Madison County.)

PROOF OF PERSONAL NOTICE.

On this 9th day of August, 1913, personally came James Minshall who being duly sworn according to law, deposes and says that on the days hereinafter named, he served the annexed notice on the persons hereinafter named, by delivering to each person opposite whose name appears "D" a true copy of the annexed notice; and on those opposite whose name appears "R" by leaving the same at their usual place of residence.

NAME OF PERSON SERVED.	How Served, D. or R.	WHEN SERVED.
Wm. B. Stone	D	Aug. 9 th
Herbert Harper	D	" "
Pearl Harper	D	" "
Wm. A. Campbell	D	" "
Grace Hamilton	D	" "
Anna Minter	D	" "
John Minter	D	" "
George Castle	R	" "
Mike Looney	R	" "
Peter Dorn	D	" "
Elmore Peters	D	" "

Filed Aug. 9th, 1913, H. M. Chaney, Auditor, Per B.

and further this deponent saith not.

James Minshall.

Sworn to by James Minshall before me, and by him subscribed in my presence, this 9 day of Aug. 1913.

#

Ella Blizzard, Deputy County Auditor.